Saint Joseph's National School

2.100m high, proposed new rendered B/S 215mm block wall

Proposed new soakaway of 225mm diameter pipes surrounded with drainage stone

Proposed new ACO drain to connect to new soakway

2.100m high, proposed new rendered B/S 215mm block wall

Proposed new ACO drain to connect to new soakway

New bonded bead gravel surface to path

New bonded bead gravel surface to path

2.100m high, proposed new rendered B/S 215mm block wall

Proposed new pedestrian gate to replace existing
NO ACCESS

Proposed planter box to top of wall

Proposed new 800mm high, lighting bollard

Drought resistant plants to proposed new planter, compatible with the objectives of the National Pollinator Plan

Proposed new ACO drain to connect to new soakway

Proposed CCTV camera located on lamp standard

Possible location of old well, to be marked with an information plaque.

500mm high, plastered both sides low planter wall

Natural stone bench to top of wall

Natural stone plinth to sign

Bonded bead gravel surface

3 sided information signage post

Natural stone plinth edging

1.200m high, traditional wrought iron effect "Estate Fencing"

Planter bed

1.200m high, traditional wrought iron effect "Estate Fencing"

Existing footpath to be raised and regraded to allow surface water to drain

Existing kerb to be taken up and replaced. Slots are to be incorporated into the kerbs to allow surface water drain to grassed area

1.200m high, traditional wrought iron effect "Estate Fencing"

Proposed new lighting bollard

Proposed new 2.100m high block wall.
Plastered both sides and capped.
Option of 2.100m high concrete post and panel fence if a block walls presents too high a risk to the existing tree roots.

Site Layout - Area 2 1:100

NOTES

1. This drawing is the property of Carlow County Council, it is a confidential document and must not be copied, used, or its content divulged without prior written consent.
2. DO NOT SCALE, use figured dimensions only, if in doubt ask.



Keyplan n.t.s.

Tailte Éireann Ordnance Survey, Land Registration, Valuation, Surveying
Includes Ordnance Survey data reproduced under Licence Number CYAL50379453
© Tailte Éireann – Surveying

No.	Date	Amendment / Issue	App
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-

CARLOW COUNTY COUNCIL
URDF & Special Projects
Castlehill Centre, Castle Hill, Carlow
Phone: (059)9170300 Fax: (059)9138206
Email: urdf@carlowcoco.ie
Engineers Ireland
Carlow Local Authorities, A CPD Accredited Company

Project:
Carlow URDF
Rail Link Project
-
-

Title:
GA Site Layout
Area 2 (1:100)
-
-

Drawn by:	CM	Job No:	202028
Checked by:	-	Dwg.loc:	J:\Carlow\202028 Rail Link Project\CAD\002 DESIGN
Approved by:	-	Drg. No:	218
Scale:	1/100 @A0	Rev:	-
Date:	06-11-2023		